



**TOWN OF STRATFORD
BID #2016-021**

**ADDENDUM #2
Issued 5/23/16**

Stage Curtains for Public Schools

All 4 schools:

Main traveler and valance made from 25 ounce IFR material and all other curtains and valances on each stage 22 ounce IFR material.

All tracks re-roped.

Upgrade all passing points and hanging points to current standards.

Update all rigging (except at Bunnell).

Update all clamps

Johnson House:

Front curtain and valance the dimensions would be 17 feet high, 19 feet wide each (2 of them) for the main curtain-4 feet high and 34 feet wide for the valance.

Addition of a main (front) traveler and valance of 25 ounce IFR material.

Update pipes for existing 6 roto-drapes.

2, not 3, four-foot valances

Bunnell :

New track and hardware for mid-stage traveler

Flood:

Add hanging points for side legs

Add 5 pipes, 21 feet long, to run horizontally for additional hanging points.

Michael Bonnar, Purchasing Agent