

September 1, 2016

ADDENDUM 1
East Main St Sidewalk Reconstruction
Bid No. 2016-041
Contract No. 2016-01

The following changes, and/or additions are hereby made to the bid documents for **East Main St Sidewalk Reconstruction** Contract No. 2016-01:

A1. Bid Form revision 1 which changes Item No 2 to Remove Existing Bituminous Concrete Curb and deletes Item No 19, Remove existing Concrete Curbing, .

Attached: revised Bid Form

UNIT BID FORM
East Main St. Sidewalk Replacement

Contract #2016-01

August 2016 rev 9-1-16

ITEM NO	DESCRIPTION	UNIT	EST. QTY.	UNIT COST	TOTAL
1	Remove 4' Concr. Sidewalk & curb Complete	SF	1880		
2	Remove Existing Bituminous Concrete Curbing, Complete	LF	106		
3	Earth Excavation to Allow for Wider Width Sidewalk and subbase removal if needed, Complete	CY	60		
4	Place processed aggregate base, Complete	CY	120		
5	Install 5' Wide, 5" Thick Concrete Sidewalk, Complete	SF	1500		
6	Install 5' Wide, 6" Thick Concrete Sidewalk /driveway apron, with wire mesh, Complete	SF	850		
7	Install 4' Wide, 4" Thick private Concrete Sidewalk, Complete	SF	800		
8	Install 6" W x 18" H Concrete Curbing, Complete	LF	470		
9	Saw Cut Bituminous Concrete / Concrete Driveway, Approach, Complete	LF	100		
10	Saw Cut Road Pavement, Complete	LF	470		
11	Remove Bituminous Concrete Driveway, approach, walk, or parking area Complete	SF	950		
12	Remove existing Bituminous Concrete Pavement in Roadway, Complete	SF	2000		
13	Install 5" Thick Bituminous Concrete Binder Course, S1.0, Complete	SY	225		
14	Install 4" Thick Bituminous Concrete Finish Course, S0.5, Complete	SY	225		
15	Remove Existing Storm MH section and Reset for new gutter line and grade. Replace with Type C Catch Basin Frame, Adjusted to new Line and Grade, Complete	LS	1		
16	Install 6" Bituminous Concrete Lip Curbing, Complete	LF	40		

17	Reset Valve boxes to grade	EA	5		
18	Reset Existing Sanitary Sewer MH Frame and Adjust to New Line and Grade, Complete	EA	1		
19	Remove Existing Concrete Curbing, Complete	LF	106		
20	Install Handicap Ramp Truncated Dome Detectable Warning Surface, Complete	EA	1		
21	Maintenance and Protection of Traffic	LS	1		
22	Remove and Rebuild Loose Block Wall behind new sidewalk, Complete	LS	1		
23	Install Haybale check or siltfence in CB, as directed, Complete	LF	15		
24	Remove and Relocate Plants and Shrubs, and Replace Mulched Areas, Complete	LS	1		
25	Loam and Seed, Complete	SY	30		
		TOTAL BASE BID			

see next page

